Serial No.	Description of work	Per	Quantity
15	Teakwood work wrought and put up with only Purlins ..	C.ft.	689·99
15a	Roofing with Mangalore tiles on teak reepers, etc., complete ...	Sqr.	120·90
16	Ridge tiles set in mortar and pointed with cement ...	R.ft.	365
17	Valleys teakwood planking 1" thick	S.ft.	297
18	Continuous zinc sheets for valleys	,,	297
19	Teakwood eaves board 9"×1" with silicate painting and bordering.	R.ft.	264
20	Teakwood large board, if necessary in rear verandah ...	Each	6
21	Plastering with chunam, two coats	Sqr.	260·44
22	White and colour washing as per plastering	,,	260·44
23	Cornice 12"×9" thick at eaves with string course ...	R.ft.	540
24	Parapet wali	,,	16
25	Chunam band mixed with cement around windows ..	,,	1,364
26	Forming panels below windows	S ft.	273
27	Flooring with Cuddapah slabs 1½" thick over 3" concrete bed, pointed with cement.	Sqr.	18·70
28	Crown of arches and forming panels, pillars of wings in front, etc.	Lump	sum
29	Flooring with square Mangalore tiles on 3" concrete bed and pointed with cement.	Sqr.	59·82
30	Providing straps, bolts, etc., to pillars	Each	26
31	Silicate painting, two coats	Sqr.	44·58
32	Ornamental cast iron semi-circular over gate in passage ...	S ft.	14
33	Double asbestos sheet screen with teakwood	,,	417
34	Providing wooden blackboard similar to the one in Bangalore High School.	Lump	sum
35	Providing name board and for foundation stone laying ceremony	Lump	sum
36	Sundry and unforeseen charges		Do
37	Opening out an approach road from the junction to the school ...		Do
38	Ornamental work		Do
39	Constructing a latrine of 8 seats		Do
40	Temporary establishment		Do
41	Laying 9" S. W. drainage pipe diagonally below basement from the open yard at N. E. corner 150' long.		Do
42	Constructing a tiffen shed		Do
43	Do well		Do
44	Earthwork excavating high ground at left side		Do
45	Earth filling and turfing		Do
46	Flues chimney arrangement hoods, etc., in the preparation room		Do
47	Cost of constructing masonry gallery in the Lecture Hall and Natural Science (3' wide and 8" rise of four steps complete.		Do
48	Polished Cuddapah or granite slab platform at a height of 2'—10" from the ground around the balance room with brackets complete.	S.ft.	32
49	Mangalore pattern glass tiles over roof in balance room and store room.	No.	12

L. A. H. WINCKLER,
Executive Engineer.

KOLAR DIVISION.

Notice dated 31st May 1928.

The attention of the public is invited to the Notification published in the *Mysore Gazette* Part VI pages 542 and 543 calling for tenders for Restoring Pathanhalli Ganganaikanakunte tank Registered No. 68 of Goribidnur Taluk 7th June 1928.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

SPECIAL DIVISION, MYSORE.

Abstract Notification.

Attention of the public is invited to the notification published on Pages 550 to 553, of Part VI of the *Mysore Gazette*, dated 7th June 1928, calling for tenders extending the Hotel Metropole Building at Mysore. The last date for presentation of the tenders is 22nd June 1928.

V. V. KARVE,
Executive Engineer,
Special Division.